

Addendum 1

Project # 02/2019 New Security Fence (Westgate)

Addendum to Existing RFP

Scope of Works

4.2. All vertical poles to be schedule 40 x 3" galvanized and installed in the earth with 3000 psi concrete a minimum of 36". Poles to be 8' c/c.

Appendix D contradicts with 4.2.

Disregard the specifications of the poles stated in Appendix D and use 4.2.

4.3. Security Fence to be 10' high x 6 guage galvanized with openings of 2½" x 2½".

Amend size of opening from 2½" x 2½" to 2" x 2".