Department of Public Lands & Buildings

ADDENDUM No. 2

DATE:	**Thursday December 9th, 2021**
METHOD OF DELIVERY:	**Government Portal, Procurement Notices**
PROJECT NAME & NO.:	**Lefroy House Dining Room, Kitchen, Break Room and Pantry – Renovations:**
TO:	**All Bidding General Contractors**

The following information supplements and/or supersedes the Tender documents dated November 2021

This Addendum forms part of the contract documents and is to be read, interpreted and coordinated with all other parts. The cost of all work contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above named project to the extent referenced and shall become part thereof. Acknowledge receipt of this addendum by inserting its number and date on the Request for Proposal. Failure to do so may subject the bidder to disqualification.

No. 2:

DESCRIPTION: DRAWING CLARIFICATIONS:

- Drawing Sheet Numbers D1.1, A1.2, A1.5, A1.6, A1.12, MEP1.0 -1, M0.0, M2.0, M3.0, M3.1: Contractor to undertake all works as detailed to Corridors G39A and G39B".

- Drawing Sheet Numbers A1.2, A1.5MEP1.1: Contractor to include for removal and disposal of existing drywall ceiling to Corridor G39B and replacing with new drywall ceiling as specified for Corridor G39A.

- Drawing Sheet Numbers A1.2 Contractor to remove <u>all</u> plaster/render to the Dining Room walls. Thereafter re-plaster <u>all</u> walls including for Xypex as specified to the interior side of all external walls.

- Drawing Sheet Numbers D1.1, A1.2, A1.4, A1.5: Contractor to include to chase (bury) all conduits into the masonry walls.

- Drawing Sheet Numbers A1.2-1: <u>Note</u> all works to gutters and rainwater leaders will be undertaken by the owner.

- Drawing Sheet Number A1.2, D1.1, D1.3,: Contractor to include for disposal of all timber shelving in the Pantry and installing new metal shelving as supplied by the owner

End of Addendum 1